



TECH TIPS

Dixie Part Numbers: A-1759 A-80221 TBA

Applications: 2007 – 2009 Audi Q7

Condition: The operator of the vehicle may complain that the generator warning light is illuminated, that there is noise coming from the engine and that there is increased effort required to steer.

Cause: A potential cause for the above condition is a broken tension spring in the belt tensioner.

Correction: The manufacturer has revised the belt and tensioner. Follow the manufacturer's recommended procedures for inspecting and changing the required parts when applicable.

