



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2010 Chevrolet Impala

Condition: The operator of the vehicle may complain that the engine fails to crank or start. The solenoid is still functioning as an audible click is present.

Cause: A potential cause for the above condition is an improper ground connection on the transaxle (connection G111).

Correction: Follow the manufacturer's recommended diagnostic and repair procedures when applicable.

