



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2007 Saturn Aura Greenline Hybrid™
2007 Saturn Vue Greenline Hybrid™

Condition:
The battery and/or check engine light may come on. Using a scan tool may reveal codes P1A59 alone or with a second code of P1A5A.

Cause:
A possible cause could be module voltage imbalance or corrosion.

Correction:
If the hybrid module voltage imbalance exceeds 0.6V or if corrosion is present the 3 batteries must be replaced following the manufactures recommended procedures.

