



TECH TIPS

Dixie Part Numbers:	A-1548	A-1708	A-1738	A-1758
	A-6548	A-80360	S-1468	S-1490
	S-1511	S-1525	S-8997	S-80060
	S-80280	TBA		

Applications: 2007 – 2010 Saturn Outlook
2007 – 2011 Cadillac Escalade
2007 – 2011 Chevrolet Avalanche
2007 – 2011 Chevrolet Silverado
2007 – 2011 Chevrolet Suburban
2007 – 2011 Chevrolet Tahoe
2007 – 2011 GMC Acadia
2007 – 2011 GMC Sierra
2007 – 2011 GMC Yukon
2007 – 2011 GMC Yukon Denali
2009 – 2011 Chevrolet Traverse

Condition: The operator of the vehicle may complain of a dead battery, that the vehicle will not crank or start, and/or an odour from the heating/cooling system (HVAC).

Cause: A possible cause for the above conditions is the HVAC after-blow function. The blower fan calibration file may cause the motor to operator, after the ignition is off in a series of cycles, which may drain the battery. This condition may have inadvertently been created by dealers installing a new calibration file that the manufacturer had recommended.

Correction: Follow the manufacturers recommended diagnostic and repair procedures, which include verifying that the after-blow calibration file is disabled on customer vehicles where dead/low batteries have been an issue.