



# TECH TIPS

**Dixie Part Numbers:** S-1406, S-1424, S-1427 and S-1458

**Applications:** 2000 – 2001 Pontiac Bonneville  
2001 Oldsmobile Aurora

**Condition:** Some vehicle operators may complain of an intermittent no start and no crank condition on the vehicle.

**Cause:** A possible cause for the above condition is plastic particles inside the ignition switch interfering with the contacts.

**Correction:** The manufacturer has updated the factory-installed switch with part number 25721650 to correct this problem. Follow the manufacturer's recommended procedures for changing the switch.

