



TECH TIPS

Dixie Part Numbers: S-1422

Applications: 2004 Pontiac Aztek

Condition: The operator of the vehicle may complain that the vehicle stalls intermittently for no apparent reason and may crank with out starting.

Cause: A potential cause for this is the ignition relay contacts may have a high resistance affecting the signal back to the Powertrain Control Module.

Correction: Follow the manufacturer's recommended procedures for inspecting and replacing the ignition relay. Please note that the NHTSA issued a campaign, ID number 05V157000 to address this issue.

