



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2008 – 2009 Pontiac G8 3.6L

Condition: The operator of the vehicle may complain that the accessory drive belt squeals, generally when the engine is cold and after the first few minutes after starting the engine.

Cause: The manufacturer has identified several manufacturing related issues that may cause the above condition including:

- The air conditioning compressor drive pulley not being properly aligned.
- The power steering pump runout being not within operating parameters (run out out).
- The power steering pump pulley rib height may be unevenly worn

Correction: Follow the manufacturer's recommended diagnostic and repair procedures.

