



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2002 – 2004 Orion V with Detroit 50G engines
2002 – 2005 Orion VI with Detroit 50G engines
2002 – 2005 Orion VII with Detroit 50G engines

Condition: The operator of the vehicle may complain that the charge warning system repeatedly fails and/or the charge light comes on intermittently.

Cause: A potential cause for the above condition is a fault in the low-pressure natural gas regulator. The factory supplied regulator seal, when exposed to higher than expected temperatures, allows coolant to leak into the alternator and terminals.

Correction: The manufacturer has released an improved low-pressure regulator gasket to correct this condition.

