



TECH TIPS

Dixie Part Numbers: A-1548 A-1645 A-1705 A-1758
 A-6548 S-1468 S-1490 S-1511
 S-80060 S-80302

Applications: 2007 Chevrolet Avalanche
 2007 Chevrolet Silverado
 2007 Chevrolet Suburban
 2007 Chevrolet Tahoe
 2007 GMC Sierra
 2007 GMC Yukon
 2007 GMC Yukon XL

NOTE: In applicable to applications with the radio option US8 or US9.

Condition: The operator of the vehicle may complain of an intermittent dead battery, a failure to start or premature alternator failure.

Cause: A potential cause for the above condition is that the radio option may not shut down and go into the sleep mode, resulting in excessive parasitic drain on the system.

Correction: The manufacturer has released a new calibration file to correct this problem. Follow the manufacturer's recommended procedures to diagnose and correct this problem.