



# TECH TIPS

## Dixie Part Numbers:

S-2057	S-2059	S-2069	S-2070	S-2071	S-2079
S-2081	S-2082	S-2095	S-2098	S-2099	S-2124
S-2125	S-8423	S-80259	S-80291		

**Applications:**

- 1997 – 2006 Ford Expedition
- 1997 – 2006 Ford F-Series Pickup
- 1997 – 2007 Ford Crown Victoria
- 1997 – 2007 Mercury Grand Marquis
- 1998 – 2006 Ford Econoline – E-series Van
- 1998 – 2006 Lincoln Navigator
- 2002 – 2007 Ford Explorer
- 2002 – 2007 Mercury Mountaineer
- 2003 – 2005 Lincoln Aviator

**Conditions:** The operator of the vehicle may complain of a no crank, no start condition.

**Cause:** A potential cause for the above conditions is an open circuit between the starter motor and starter relay.

**Correction:** A pigtail harness is available to correct the problem the manufacturer part number is 6U2Z-14S411-NA. Dixie has a repair harness available which includes heat shrink tubing and the terminal connectors. The Dixie part number is 79502-091. The harness is only intended to repair the relay circuit and not the large battery post circuit terminal.

Rev: 20111122 Update Application and SKU listing