



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2009 Lincoln MKS

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- the vehicle fails to crank
- the starter drive chatters in and out

Cause: A potential cause for the above conditions is a low battery, which may be due to an error in the power train control module calibration file.

Correction: The manufacturer has updated the calibration file to correct the problem (version B58.3). Verify that the latest calibration file has been installed. When servicing the vehicle there will be no note of this on any of the under hood decals.

