



# TECH TIPS

**Dixie Part Numbers:**      A-469              A-470              A-472  
   A-6374              A-6398

**Applications:**      1994 – 2001 Land Rover Range Rover  
   1998 – 2001 Land Rover Discovery II

**Condition:**      The operator of the vehicle may complain of one or more of the following conditions:

- The belt chirping under load
- The belt slipping
- The belt requiring frequent replacement.

**Cause:**      A potential cause for the above conditions is a faulty idler pulley that may cause the belt to wear and slip prematurely.

**Correction:**      Inspect under the hood of the vehicle to see if there is a decal referring to service campaign H369, if so then the faulty idler pulley has already been replaced, if not, follow the manufacturer's recommended replacement procedures.

