



# TECH TIPS

**Dixie Part Numbers:** Not Applicable

**Applications:** 2007 – 2008 Ducati 1098  
2007 – 2008 Ducati 1098 Tricolore  
2007 – 2008 Ducati 1098S  
2008 – 2009 Ducati 1098R  
2008 – 2009 Ducati 848

**Condition:** The operator of the vehicle may complain of erratic charging up to and including failure of the charging system.

**Cause:** A potential cause for the above condition is the rectifier/regulator module located below the seat. The manufacture has identified that excessive heat from the exhaust may have a negative affect on the rectifier/regulator module.

**Correction:** The manufacturer suggests replacing the regulator, installing a heat guard between the regulator and exhaust system and a modified battery support.