



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2010 BMW 128i
2010 BMW 135i
2010 BMW 323i
2010 BMW 328i (including x Drive models)
2010 BMW 335i (including x Drive models)
2010 BMW 335is
2010 BMW X5
2010 BMW X6

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- The engine cranks hard or slowly
- The starter fails to crank
- The battery is low or dead
- The tailgate, tailgate window or trunk release fail to operate
- The electronic glove compartment does not function

Cause: A potential cause for the above is a software error in the JBBFE-3R (Junction Box) control module that causes the module to not enter the sleep mode.

Correction: Follow the manufacturer's recommended procedures for diagnosing and repairing the above concern.

