



TECH TIPS

Dixie Part Numbers: A-80267

Applications: 2008 Mazda Tribute 2.3L with a manual transmission

Condition: The operator of the vehicle may complain that the vehicle has a belt squeal or chirp during any one of the following conditions:

- When initially moving in first gear.
- Between shifts.
- During cold temperature starting.
- When there are high electrical demands.

Cause: The accessory drive belt is slipping due to an improper design/manufacture.

Correction: Follow the manufacturer's recommended procedures and replace the belt with the current design. The manufacturer's part number is ZZC7-18-381.

