



TECH TIPS

Dixie Part Numbers:

S-80195	TS-1603	TS-1747	TS-1800	TS-1823	TS-1872
S-80223	TS-1604	TS-1751	TS-1801	TS-1824	
TS-1501	TS-1742	TS-1794	TS-1804	TS-1871	

Applications: 2008 – 2012 Freightliner Cascadia*
2008 – 2012 Freightliner Century Class*
2008 – 2012 Freightliner Columbia*
2008 – 2012 Freightliner Coronado*
2008 – 2012 Sterling A-Line*
2008 – 2012 Sterling L-Line*
2009 – 2012 Western Star Constellation*

***Note with Detroit Series 15 or Detroit Series 16 Engines**

Condition: The operator of the vehicle may complain of intermittent cranking, a failure to crank or an engine compartment fire.

Cause: A potential cause for the above conditions is that a rubber support bracket bolt may come loose, back out, and short against the un-fused battery cable. This may allow the cable to chafe against the bolt and could cause a short circuit.

Correction: Follow the manufacturers recommended diagnostic and repair procedures when applicable.