



# TECH TIPS

**Dixie Part Numbers:** TBA

**Applications:** 2010 – 2012 Chevrolet Express with Gasoline Engine  
2010 – 2012 GMC Savana with Gasoline Engine

**Conditions:** The operator of the vehicle may complain of a chirp sound while starting the engine in colder temperatures. The technician may trace the sound to the power steering pump.

**Cause:** A potential cause for the above condition is the viscosity of the power steering fluid.

**Correction:** Follow the manufacturers recommended power steering fluid replacement procedures which include flushing out the factory installed fluid and replacing it with the appropriate replacement fluid, available through the dealership network:

|                            |          |
|----------------------------|----------|
| Canada (and cold climates) | 10953471 |
| US (and warmer climates)   | 12345867 |