



TECH TIPS

Dixie Part Numbers: S-80135 TS-1501 TS-1512 TS-1742
TS-1794 TS-1796 TS-1824 TS-1873

Applications: 2002 – 2004 Orion V with Detroit 50G engines
2002 – 2005 Orion VI with Detroit 50G engines
2002 – 2005 Orion VII with Detroit 50G engines

Condition: The operator of the vehicle may complain that the charge warning system repeatedly fails and/or the charge light comes on intermittently.

Cause: A potential cause for the above condition is a fault in the low-pressure natural gas regulator. The factory supplied regulator seal, when exposed to higher than expected temperatures, allows coolant to leak into the alternator and terminals.

Correction: The manufacturer has released an improved low-pressure regulator gasket to correct this condition.

20191017 Updated Dixie part numbers

REV: 20100701

Courtesy of Recall Cast

TSB_163

Dixie *Tech Tips* are intended for use by professional technicians and are not for the general public. They are written to inform technicians of conditions that may exist or as a guide to aid in diagnosing and servicing a vehicle. All references to original equipment manufacturers, vehicle manufacturers and any other Trademark names are for the sole purpose of identifying the vehicle and or part that the *Tech Tip* applies to. This document is property of Dixie Electric Ltd. and is not to be copied or distributed without written permission.