



# TECH TIPS

**Dixie Part Numbers:** TBA

**Applications:** 2009 Mazda Tribute 2.5L (built between October 27, 2008 and November 28, 2008)

**Condition:** The operator of the vehicle may complain that upon a cold start up the accessory belt chirps, whines or whistles. The noise will be most noticeable when decelerating from 1500 RPM to 1100 RPM.

**Cause:** A potential cause for the above condition is a manufacturing flaw in the idler pulley.

**Correction:** Follow the manufacturer's recommended procedures for diagnosing and replacing the pulley and belt if required. The manufacturer's part number for the updated idler assembly is ZZC2-15-940.

