



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2009 BMW 750i 4.4i
2009 BMW 750i 4.4Li

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- the engine is hard to start
- the engine fails to start
- the engine runs rough
- the engine lacks or loses power

When the key is cycled to restart the engine the problem goes away.

The technician may observe code 1100001 stored in the system.

Cause: A potential cause for the above condition is fuel system vapour lock, which then causes a drop in the low side fuel pressure.

Correction: The manufacture has released an update to the calibration file to correct this issue.