



TECH TIPS

Dixie Part Numbers: S-6259 TBA

Applications: 2008 – 2010 BMW 760i
2008– 2010 BMW 760Li

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- The vehicle intermittently has an extended crank cycle.
- The vehicle intermittently does not start.
- The vehicle loses power while driving.

The technician may observe code FC 200908 stored in the engine control module (DME).

Cause: A potential cause for the above conditions is a faulty fuel pressure regulator.

Correction: Follow the manufacturer's recommended procedures for inspecting, testing and replacing the fuel pressure regulator when required.

