



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2011 BMW ActiveHybrid7
2011 BMW ActiveHybrid7L
2011 BMW 530d
2011 BMW 535d
2011 BMW 535i
2011 BMW 550i
2011 BMW 730i and 730Li
2011 BMW 740i and Li
2011 BMW 750i and Li
2011 BMW 760Li

Condition: The operator of the vehicle may complain that the message “Replace Battery” is displayed in the Message centre. The technician may observe fault 213B01 – Power Management, battery status detected: battery is faulty” stored in the system.

Cause: A potential cause for the above condition is a software flaw.

Correction: Follow the manufacturer’s recommended procedures to update the software. This includes running the battery replacement program at least twice and waiting 20 seconds or more between running the updates.