



TECH TIPS

Dixie Part Numbers: S-6262 S-6263 S-6290 S-6558
S-6561 TBA

Applications: 2008 – 2014 Audi A4 with manual transmission
2008 – 2014 Audi A5 with manual transmission
2008 – 2014 Audi S4 with manual transmission
2008 – 2014 Audi S5 with manual transmission

Conditions: The operator of the vehicle may complain that the engine fails to start or only starts with the clutch pedal pushed extremely hard. The technician may notice that if the clutch slave or master cylinders have been replaced, the problem is still not resolved.

Cause: A potential cause for the above conditions is air in the hydraulic system.

Correction: Follow the manufacturer's recommended procedures to bleed the hydraulic system. This will require 2 people... or perhaps one and a brick... the procedure indicates to have the clutch pedal depressed and then with the pedal depressed to open the master cylinder bleeder valve.