



TECH TIPS

Dixie Part Numbers: A-8478 A-8479

Applications: 2000 – 2001 Mazda Millenia VIN numbers JM1TA22xx11703089 and lower.

Condition: Th operator of the vehicle may complain that when first started when the engine is cold and shifted into gear with the air conditioning on that there is a belt squeal or chirp.

Cause: A possible cause for the above condition is that the initial belt material contained to much wax resulting in slippage during cold operation.

Correction: The manufacturer has changed the material in the belt, the revised belt part number is KJ02-18-381B.

