



TECH TIPS

Dixie Part Numbers: S-80392 S-80400

Applications: 2006 Land Rover Range Rover with the optional supercharger (VIN 6A194480 – 6A239036)
2006 Land Rover Range Rover Sport with the optional supercharger (VIN 6A900129 – 6A983117)

Condition: The operator of the above vehicle may complain that the engine may be hard to start or runs rough when started cold.

Cause: A potential cause for the above condition is an outdated calibration file in the engine control module and transmission control module.

Correction: Follow the manufacturer's recommended diagnostic procedures and ensure that patch file 9 or higher have been installed in the system.

