



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2009 Acura RL
(VIN JH4KB26xx9C000001 to H4KB26xx9C001588)

Condition: The operator of the above vehicle may complain that the engine cranks for an extended period when warm (the engine run for longer than ½ hour).

Cause: A possible cause is inadequate oxygen being supplied to the intake manifold due to a program flaw in the control module.

Correction: Follow the manufacturer's recommended procedures to ensure that the fuel injection control module (PGM-FI) has the correct updated software, V6.14.06 or later. Update the software following the manufacturer's recommended procedures if required.

