



TECH TIPS

Dixie Part Numbers: S-8682 TBA

Applications: 2007 – 2009 Jaguar XK

Condition: The operator of the vehicle may complain of that the engine fails to crank intermittently after shutting the engine off for a short period (10 minutes) and that the remote door unlock had also not functioned. After waiting another 10 minutes everything functions as normal.

Cause: A potential cause for the above condition is a software issue between the central junction box and the auxiliary junction box.

Correction: The manufacturer has released a software update to resolve the above issue. Follow the manufacturer's recommended procedures to update the system with patch file 3 or later.

