



TECH TIPS

Dixie Part Numbers: A-8937 A-9500 S-8588 S-8589

Applications: 2006 – 2007 Hyundai Tucson with a factory installed MP3 audio player (M280).

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- The engine fails to crank or cranks slowly.
- That the battery is discharged after the vehicle has not been driven for 2 or 3 days

Cause: A potential cause for the above condition is that the factory installed radio may have excessive quiescent mode (sleep mode) draw.

Correction: The manufacturer has issued replacement remanufactured radios, part number 00201-T5000-FLT to correct this problem.

