



TECH TIPS

Dixie Part Numbers: A-8203

Applications: 1983 – 1985 Mitsubishi Starion

Condition: The technician may observe deteriorated battery cable from the alternator to the battery.

Cause: A potential cause for the above condition is that the factory installed battery cable was undersized for the alternator amperage, resulting in too much current flowing through the wire generating excessive heat.

Correction: The manufacturer has released an upgraded battery cable wiring harness to more adequately handle the alternator output. Follow the manufacturers recommended procedures when replacing the battery cable.

