



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2009 – 2010 Dodge Challenger
2009 – 2010 Dodge Charger
2009 – 2010 Chrysler 300

Condition: The operator of the vehicle may complain that the remote start feature does not function on an intermittent basis.

Cause: The above condition may be caused by the calibration file load in the Totally Integrated Power Module.

Correction: Follow the manufacturer's recommended diagnostic and repair procedures which include scanning the system for diagnostic trouble codes and verifying if the latest calibration files have been used. **If updating the calibration files ensure that the model year for the vehicle is correct as there are two separate calibration files!**

