



TECH TIPS

Dixie Part Numbers: TBA

Applications: 2011 Toyota Sienna

Conditions: The operator of the vehicle may complain that the battery loses its charge overnight with no accessories left on. The technician may observe a drain in excess of 2 amps.

Cause: A potential cause for the above condition is a stuck or faulty air conditioner clutch relay.

Correction: Follow the manufacturers recommended diagnostic and repair procedures.

