



TECH TIPS

Dixie Part Numbers: NA

Applications: 2006 - 2008 Lexus RX 400h
2006 – 2008 Toyota Highlander HV
2008 Lexus GS450h
2008 Lexus LS 600h
2008 Toyota Camry HV
2008 Toyota Prius

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- The engine runs too long or more frequently than normal.
- The fuel economy has reduced
- The transmission gear noise is more noticeable.

Cause: If the 12-volt battery is either disconnected from the system or if the voltage drops below 7 volts for any reason the idle speed will not retain its settings.

Correction: Whenever the 12-volt system is disconnected for any reason (such as changing the alternator or starter) the idle speed control must be reprogrammed. Follow the manufacturer's recommended procedures for performing the *ICS Learning Procedure*.

Revisions: 20091116 Added 2008 application listings

REV: 20091116

Courtesy of APRA

TSB_839.doc

Dixie *Tech Tips* are intended for use by professional technicians, and are not for the general public. They are written to inform technicians of conditions that may exist or as a guide to aid in diagnosing and servicing a vehicle. All references to original equipment manufactures, vehicle manufactures and any other Trade Mark names are for the sole purpose of identifying the vehicle and or part that the *Tech Tip* applies to. This document is property of Dixie Electric Ltd. and is not to be copied or distributed without written permission.