



TECH TIPS

Dixie Part Numbers: A-80032

S-80319

Applications: 2007 Acura MDX

Condition: The operator of the vehicle may complain of a low or dead battery, alternator premature failure or a failure to start.

Cause: A possible cause for the above conditions is a sticking power door lock switch in either the driver's door or the passenger's door.

Correction: Follow the manufacturer's recommended diagnostic and repair procedures which may require realigning or replacing the door lock switch bracket with new ones. The manufacturer's part numbers are 83590-STX-A11 for the driver's side or 83540-STX-A11 for the passenger's side door.

Rev: 20101014 Original release of TSB-8030
20121211 TSB-849 and TSB-8030 consolidated to TSB-849. TSB-8030 cancelled.