



TECH TIPS

Dixie Part Numbers: S-80072

Applications: 2005 – 2007 Toyota Tacoma 4.0L (1GRFE Engine)

Condition: The operator of the vehicle may complain of an intermittent no start condition.

Cause: A possible cause could be an out of date calibration file. The vehicle manufacturer has released an updated calibration file for the Powertrain Control Module to address this issue.

Correction: Before performing any work check the under hood decal to see if the updated calibration file has been loaded into the Powertrain Control Module. If it has there will be a reference to *TSB EG011-07* or higher. If the calibration has not been done, follow the manufacturer's recommended procedures for updating the calibration file in the Powertrain Control Module.

