



TECH TIPS

Dixie Part Numbers: S-8194 S-8221 S-8234 S-8338

Applications: 1986 – 1987 Mazda B2000 2.0L
1988 – 1989 Mazda B2000 2.2L
1988 – 1989 Mazda B2000 2.6L

Condition: The operator of the vehicle may complain of intermittent no start conditions.

Cause: A potential cause for the above condition is a poor electrical connection in the main fuse block.

Correction: To correct this problem, the main fuse block should be removed from the mounting bracket. All connections must be tested using a digital voltmeter and ensure that the connections are solid, in good condition. Clean, tighten and repair any connection that is not in good condition.

