



TECH TIPS

Dixie Part Numbers: A-8162 S-8246

Applications: 1989 – 1990 Nissan Maxima

Condition: The operator of the vehicle may complain of one or more of the following conditions:

- A weak or low battery.
- A failed battery.
- Hard or slow cranking

The technician may observe diagnostic trouble code DTC0013.

Cause: A potential cause for the cylinder head temperature sensor wiring harness. The harness can short out and cause the cooling fans to run until the battery is dead.

Correction: Inspect and repair or replace the wires and sensor. Follow the manufacturer's recommended procedures for re-routing the wires away from the cylinder head.